

ACS.CCLP1 SAFETY ASSESSMENT CRITERIA INITIAL & RE-ASSESSMENT DOMESTIC LPG

CCLP1 INITIAL & RE-ASSESSMENT

Introduction

This Core assessment now incorporates the criteria for combustion performance analysis for delivery from 1st April 2012. This packaged Assessment shall be delivered from 1st April 2012 and shall be downloaded to the national database using the assessment codes CCLP1 + CPA1. This will ensure the Candidate's competence in combustion performance analysis is recognised.

CCLP1 shall be associated with at least one of CCLP1 PD, RPH, LAV, and B.

Tests gas safety competence in core LPG work.

Candidates subsequently sitting only CCLP1 B will not need to prove competency in sections related to LPG metering or the commissioning of OPSO/UPSO valves from the following competence criteria.

Group 1. Part A. Comprises:

- 1. Gas safety legislation and Standards
- 2. Gas emergency actions and procedures.
- 3. Products and characteristics of combustion (inc. combustion performance analysis)
- 3a. Characteristics of LPG.
- 3b. Supply pressures. Operation and positioning of emergency isolation, flow control and valves for cylinders.
- 3c. Cylinder location, safety and sizing.
- 5. Installation of pipework and fittings.
- 6a. Tightness testing and purging (PD, LAV and RPH).
- 6b. Tightness testing and purging (B).
- 8. Unsafe situations, use of emergency notices and warning labels.
- 11. Operation and checking of appliance gas safety devices and controls.
- 12. Chimney Standards.
- 13. Chimney inspection and testing.
- 14. Installation of open, closed, balanced and fan assisted chimneys.
- 15. Re-establish existing gas supply and re-light appliances.

CBs may adopt Competence and Criteria numbering different to that used in this document.

CB documentation may adopt wording for criteria different to that used in this document, provided the meaning is unaffected.

Range

All LPG gas fittings.

Pre-requisites *Initial* <u>All I</u>nitial Assessment require suitable proof of gas work training and experience

CCLP1 (or a suitable Changeover assessment or aligned QCF or S/NVQ) is the pre-requisite for all other domestic LPG safety assessments. *Re-assessment*

References and normative documents

MIs.

All relevant documents as listed in the Legislative, Normative & Informative Document List (LINDL), Inc.:

• BS EN ISO 10239:2014

- IGEM/UP/1B Edition 3
- HSL56
- GIUSP.
- PD 54823: 2016

ACS.SMB.003.ACRND identifies Normative Documents that should be held by ACs.

Where a reference point (REF) is listed in this criteria this is only a guide to where the criteria could be resourced, therefore the REF may not be exhaustive.

Abbreviations

AC. Assessment Centre **AIV Appliance Isolation Valve** CB. Certification Body B. Boat HP. High pressure I. Initial LAV. Leisure accommodation vehicle LDF. Leak detection fluid LP. Low pressure MIs. Manufacturer's/manufacturers' instructions OP. Operating pressure OQ. Oral questioning OPSO. Over-pressure safety cut-off PD. Permanent dwelling R. Re-assessment Ref. Reference RPH. Residential park home SSOV. Safety shut-off valve UPSO. Under-pressure safety cut-off.

1. Gas safety legislation and Standards

KNOV	VLEDGE A	ND UNDERSTANDING	REF	Ι	R
1.	HSL56:				
(i)	Reg.2	General interpretation and application 2(1) to (5)		\checkmark	
(ii)	Reg.3	Qualification and supervision 3(1),(2),(3),&(6)		\checkmark	
(iii)	Reg.4	Duty on employer		\checkmark	
(iv)	Reg.5	Materials and workmanship 5(1) to (3)		\checkmark	
(v)	Reg.6	General safety precautions 6(1) to (9)		\checkmark	
(vi)	Reg.7	Protection against damage 7(1) to (3)		\checkmark	
(vii)	Reg.8	Existing gas fittings 8(1) to (3)		\checkmark	
(viii)	Reg.25	Interpretation of Part E		\checkmark	
(ix)	Reg.26	Gas appliances - safety precautions 26(1) to (9)		\checkmark	
(x)	Reg.35	Duties of employers and self-employed persons		\checkmark	
(xi)	Reg.36	Duties of landlords 36(1) to (12)		\checkmark	

2. Gas emergency actions and procedures

KNO	WLEDGE AND UNDERSTANDING	REF	Ι	R
1(a)	priorities of actions and responsibilities		\checkmark	
1(b)	dealing with gas leakage with fire and safety/fire precautions for cylinders		\checkmark	
1(c)	dealing with gas leakage without fire:			
2.	specific gravity and its effect in relation to air e.g. search techniques		\checkmark	
3.	preventing/reducing dangerous concentrations of gas in atmosphere and at low level		\checkmark	
4.	advice to occupants		\checkmark	
5.	HSL56: Reg.9 Emergency controls 9 (5)		\checkmark	

3. Products and characteristics of combustion

PERI	FORMANCE CRITERIA	REF	Ι	R
1.	visually inspect flame picture of burners and identify those indicating:			
(i)	complete combustion		\checkmark	\checkmark
(ii)	incomplete combustion		\checkmark	\checkmark
2.	identify incomplete combustion in an open flue appliance:			
(i)	around appliance location		\checkmark	\checkmark
Issue	14.3 © ACS_SMB April 2018			-

ACS.SP	1B.004.AC.TABLE 2.CCLP1. INITIAL & RE-ASSESSMENT			
(ii)	in appliance		\checkmark	
3.	CO detectors and indicators:			
(i)	identify detectors and indicators		\checkmark	\checkmark
(ii)	installation – locations		\checkmark	
(iii)	commissioning and maintenance of detectors (audible, readable, visual)		\checkmark	
4.	Combustion performance analysis:			
(i)	inspect appliances of 3 flue types intended for combustion performance testing to		\checkmark	\checkmark
	ensure installation, flueing and ventilation are to MIs			
(ii)	inspect appliances for obvious signs of damage and factors that may affect		\checkmark	\checkmark
	combustion performance			
(iii)	check OP and/or heat input of each appliance		\checkmark	\checkmark
(iv)	light each appliance and visually inspect combustion performance		\checkmark	\checkmark
(v)	check analyser is suitable, correctly assembled and calibrated		\checkmark	\checkmark
(vi)	select correct types of sampling probe for each appliance		\checkmark	\checkmark
(vii)	turn on analyser and prepare for use to MIs		\checkmark	\checkmark
(viii)	correctly position probes for sampling products from each appliance		\checkmark	\checkmark
(ix)	adjust position of probe to obtain highest steady value of CO2 or lowest steady		\checkmark	\checkmark
	value of O2 for each appliance			
(x)	read and record CO/CO2 ratios for each appliance		\checkmark	\checkmark
(xi)	adjust and re-test appliance if CO/CO2 ratio levels are too high		\checkmark	\checkmark
KNOV	VLEDGE AND UNDERSTANDING	REF	I	R
1.	main constituents of complete and incomplete combustion		\checkmark	
2.	air requirements for complete combustion		\checkmark	
3.	causes of appliance incomplete combustion at:			
(i)	burner		\checkmark	
(ii)	combustion space		· √	
(iii)	heat exchanger		v √	
. ,	flue			-
(iv)				-
4.	symptoms of CO poisoning			/
5.	advice to a person who describes symptoms of being affected by products of		\checkmark	\checkmark
6	combustion or when indicator/detector has activated		- /	- /
6.	other sources of CO and CO ₂ in dwellings		√	
7.	ambient levels of CO in atmosphere			V /
8.	levels of CO within dwellings and effect on electronic detectors			
9.	causes of activation of CO detectors and indicators			
10.	ambient levels of CO ₂ in atmosphere			
11.	critical levels of CO ₂ that could cause vitiation effecting combustion process		V	V
12.	movement of products of combustion within properties and its effects		V	V
12a	advice to be given when a CO detector has activated		∕	\vee
13.	manufacturing standards for electronic CO detectors (alarms)			V
14.	identification of unsafe situation of combustion products that could enter a		\checkmark	V
1 -	premises		,	· /
15.	additional allowance for CO levels for gas cookers		\checkmark	\vee
16.	combustion performance analysis:		/	
(i)	re-testing appliances when new components have been fitted			
(ii)	unsafe situation category for flued appliance that fails test			
(iii)	unsafe situation category for flueless appliance that fails test			
(iv)	understanding of action levels for gas appliances		∕	
(v)	actions if CO/CO2 ratio remains above suitable performance levels after		\checkmark	
	adjustment		,	,
(vi)	types of portable combustion analysers		\checkmark	\checkmark

3a. Characteristics of LPG

KNO	WLEDGE AND UNDERSTANDING	REF	Ι	R
1.	types of commercial LPG (propane, butane)		\checkmark	
2.	storage pressures for both gas types and its relation to temperature		\checkmark	
3.	specific gravity of LPG vapour and its effect in relation to air and Natural Gas		\checkmark	
4.	vaporisation of LPG liquid and off-takes - effects of temperature		\checkmark	
5.	limits of flammability		\checkmark	
6.	calorific value		\checkmark	

3b. Cylinder location, safety requirements and sizing

KNO\	NLEDGE AND UNDERSTANDING	REF	Ι	R
1.	safety requirements, sizing of cylinders:			
(i)	sizes and marking of common Propane and Butane cylinders commercially available and recommended off-takes to match appliance demand		\checkmark	
(ii)	linking cylinders through manifolds		\checkmark	
(iii)	areas where cylinders are not to be located		\checkmark	
2.	HSL56:			
(i)	Reg.6 General Safety Precautions 6 (8)		\checkmark	
(ii)	Reg.6 General Safety Precautions 6 (9)		\checkmark	

3c. Supply pressures - operation and positioning of emergency isolation, flow control and valves for cylinders

PERF	ORMANCE CRITERIA	REF	Ι	R
1.	LPG regulators :			
(i)	turn off all appliances			
(ii)	turn off gas supply			
(iii)	zero pressure gauge and connect to appropriate test point		V	
(iv)	identify manufacture standard of regulator; re-establish gas supply, observe and record lock up pressure is in accordance with BS 6891 or BE EN 1949 (LAV)	BS 6891: 2015 10.3b & Table 7	V	V
(v)	turn on and light sufficient burners and observe and record OP is in accordance with BS 6891 or BE EN 1949 (LAV)	BS 6891: 2015 10.3a & Table 7	V	\checkmark
(vi)	remove gauge, re-seal test point and test for gas tightness		\checkmark	\checkmark
KNOV	NLEDGE AND UNDERSTANDING	REF	Ι	R
1.	recognition of supply pressures from gas storage cylinders:			
(i)	HP stage		\checkmark	
(ii)	LP stage		v	
2.	operation and positioning of gas storage cylinder fittings:		v	
(i)	pressure relief valve		\checkmark	
(ii)	cylinder valve			
3.	types and sizing of gas regulators			
4.	operation and positioning of emergency isolation valves	PC 6901		
5.	operation and positioning of automatic changeover valves for cylinders	BS 6891: 2015 E.2.3	V	
6.	HSL56: Reg.14 Regulators 14 (2) to (7)		\checkmark	
7.	min./max. outlet pressures for BS EN 12864, BS EN 13785 & BS EN 16129 regulators as listed in BS 6891	BS 6891: Table 7 & TB 080	\checkmark	\checkmark
8.	lock-up pressures for BS EN 12864, BS EN 13785 & BS EN 16129 regulators	BS 6891: Table 7 & TB 080	\checkmark	\checkmark
9.	identifying causes of over pressure conditions		\checkmark	\checkmark
10.	operation/positioning/visible indicators (where applicable) of OPSOs		\checkmark	\checkmark
11.	procedures when OPSO has operated (MI's & Gas Supplier data sheets)	MI's	\checkmark	\checkmark
12.	requirement for over pressure shut off (OPSO) devices	BS 6891: 2015 E.1.1	\checkmark	\checkmark
13.	identifying when UPSO/OPSO commissioning needs to be made	BS 6891: 2015 10.3.4	\checkmark	\checkmark
14.	safety and security of single supply gas storage vessels and controls			\checkmark
15.	safety requirements for termination location of limited relief valve	BS 6891: 2015 E.2.2 / E.2.8 Table E2	V	\checkmark
16.	requirement for under pressure shut off (UPSO) device on installations supplied by a bulk gas storage vessel	BS 6891: 2015 E.1.1	\checkmark	\checkmark

5. Installation of pipework and fittings. Range of pipe sizes: 6 mm to 28 mm

PER	FORMANCE CRITERIA	REF	I	R
1.	join threaded pipe joints using appropriate fittings, methods and agents		\checkmark	
2.	join copper or stainless steel pipe using appropriate mechanical	BS 6891 2015: 7.3	\checkmark	
	(compression) fittings, methods and agents			
3.	connect replacement HP hoses. Fabricate LP hoses using appropriate clips,		\checkmark	\checkmark
	fittings, agents			
3a.	reconnect cylinder and remove temporary earth continuity bond			\checkmark
4.	use of temporary continuity bond		\checkmark	
5.	ensure work carried out is gas tight		\checkmark	\checkmark
6.	purge meter and pipework of air (meter not applicable to (B)) Apply any protective coating (OQ)		\checkmark	\checkmark
7.	identify installation pipework safety defects			
	WLEDGE AND UNDERSTANDING	REF	V I	R
1.	copper pipe and fittings; standards, suitability and use	BS 6891 2015:		
1.	copper pipe and mengs, standards, suitability and use	6.4, 7.2, 7.3	v	
2.	flexible hoses (e.g. colour band on cooker hose) and rigid connections		\checkmark	
	standards, suitability and use			
3.	Installation of flexible hoses, tubing, assemblies and their connections:			
i	Standards	BS 6891: 2015	\checkmark	\checkmark
	L	9.1.8 & Fig 25	,	
ii	Length	BS6891: 2015 9.1.2, 9.2 & 9.3	\checkmark	\checkmark
iii	Condition	BS 6891: 2015		
	Condition	9.1.4	v	v
iv	Service life	9.1.9	\checkmark	\checkmark
4.				
5.	pipe sizing to appliance requirements – inc. theoretical exercise	BS 6891: 2015	\checkmark	
	(not applicable with 'Boats' only)	Annexe A	·	·
6.	jointing and cleaning agents for copper pipework			
7.	pipe supports, clips and fixing for copper, stainless and galvanised steel	BS 6891 2015: 8.8	√	
	pipework	Table 4	ŀ	
8.	sleeving pipework		\checkmark	
9.	precautions and protection when installing pipework		\checkmark	
10.	external surface mounted installation pipework		\checkmark	
11.	main equipotential bonding		\checkmark	
12.	precautions when using naked flames on pipework previously containing LPG		\checkmark	
13.	siting and installation for gas controls and isolation valves		./	
14.	making and breaking gas connections on appliances			
15.	ducts purposely designed to contain gas pipes			-
16.	HSL56:		v	
(i)	Reg.10 Equipotential bonding		\checkmark	
(ii)	Reg.18 Safe use of pipes 18 (1) and (2)			
(iii)	Reg.19 Enclosed pipes 19 (1) to (6)			
(iv)	Reg.20 Protection of buildings		v V	
(v)	Reg.22 Testing and purging of pipes 22 (1) to (3)			
17.	MP and LP meter locations which do not comply with BS 6400-3			\checkmark
18.	location and sizing vent pipes on MP meter installations			
19.	gas meters supplying mobile dwellings and boats			
20.	where a number of primary meters serving multi-occupancy buildings are			V V
	grouped			
21.	notices fitted to meter installations, meter housings			

6a. Tightness testing (PD, LAV and RPH). Total IV \leq 0.035 m³. OP \leq 37 mbar Up to 1¼ (steel) and/or 35 mm (copper)

PER	FORMANCE CRITERIA	REF	Ι	R
1.	Testing new and existing installations with gas:			
(i)	visually inspect the installation to ensure all sections to be tested are connected, all joints are correctly made and no open ends		\checkmark	\checkmark
(ii)	check appliances burner control taps are turned off, ensure AIVs are open and cooker fold down lids are raised to ensure the SSOV is open		\checkmark	\checkmark

ACS.SMB.004.AC.TABLE 2.CCLP1. INITIAL & RE-ASSESSMENT

	B.004.AC.TABLE 2.CCLP1. INITIAL & RE-ASSESSMENT	r	,	
(iii)	turn off the gas installation at the appropriate valve		\checkmark	\checkmark
(iv)	connect the pressure gauge to a suitable pressure test point on the outlet of the supply control valve and the final regulator		\checkmark	\checkmark
(v)	carry out a let-by test of the closed supply control valve:			
	adjust the pressure to between 7 and 10 mbar		\checkmark	\checkmark
	 reset any UPSO to release upstream pressure and re adjust if the pressure exceeds 10 mbar 		\checkmark	\checkmark
	close the supply control valve where necessary, note the gauge reading		\checkmark	\checkmark
(vi)	check for any perceptible movement (rise) of the gauge reading over the next 1 minute period (if UPSO fitted operate at the end of the 1 minute period)		\checkmark	\checkmark
(vii)	if no perceptible movement is observed then the valve is not letting by			
(viii)	if pressure rise is observed, check valve by disconnecting its outlet union and applying LDF to valve barrel (OQ if valve does not let by practically)		\checkmark	\checkmark
(ix)	on satisfactory completion of let-by test slowly raise the pressure in the installation to the appropriate tightness test pressure indicated in Table 4 (IGEM/UP/1B Edition 3)		\checkmark	\checkmark
(x)	close the supply control valve		\checkmark	\checkmark
(xi)	allow 1 minute stabilisation; if necessary re-adjust pressure to the tightness test pressure - do not proceed until a stable reading has been achieved		\checkmark	\checkmark
(xii)	check for no perceptible movement (fall) of the gauge over the next 2 minute period		\checkmark	\checkmark
(xiii)	if an installation fails test, trace and repair escape and re-test installation (OQ)		\checkmark	\checkmark
(xiv)	if tightness test is successful, remove pressure gauge and re-seal test point		\checkmark	
(xv)	test pressure test point; ECV/AECV outlet connection; regulator connections and, where appropriate, MIV connections with LDF		\checkmark	\checkmark
(xvi)	purge installation		\checkmark	
(xvii)	record test results		\checkmark	
2.	Locate and repair a gas escape		\checkmark	
KNOV	VLEDGE & UNDERSTANDING	REF	Ι	R
1.	Correct reading of pressure gauges		\checkmark	\checkmark
2.	Locating escapes		\checkmark	\checkmark
3.	Actions for dealing with valves letting by		\checkmark	\checkmark
3a.	Effects of flexible connections used to connect cylinders on let-by tests		\checkmark	\checkmark
4.	Use of electronic pressure gauge (calibration requirements)		\checkmark	\checkmark
5.	Air test pressure requirements for butane/propane installations		\checkmark	ν
5.	Installation test pressures for propane/butane			ν
7.	Permissible pressure drops for existing LPG installations with appliances IGEM/UP/1B Edition 3 (Appendix 8)		\checkmark	V
8.	Actions to be taken where a cylinder valve is found to be faulty			
9.	Actions to take ensure lock up does not affect the tightness test			
10.	Additional requirements for re-testing installations that may contain air or a gas/air mixture following an initial test		\checkmark	\checkmark

6b. Tightness testing. Boats, yachts and other vessels (the Air testing within PD54823: 2016 & N ISO 10239 are now identical, however for ease of use, detail and consistency the use of PD 54823: 2016 is referenced)

	ORMANCE CRITERIA 823: 2016 Small craft – LPG systems	REF	I	R
1.	LPG installation system tests with appliances connected (using air)			
(i)	test with air from gas regulator connection to closed burner valves at appliances	PD 54823 10.2.3 (a)	\checkmark	\checkmark
(ii)	cap off all other open points but the one point to insert air	PD 54823 10.2.4. (b)	V	V
(iii)	connect a suitable calibrated "U" gauge and a in line test tee if needed.	PD 54823 10.2.4. (c)	V	V
(iV)	introduce air into system to a test pressure 3 $$ x NOP for gas to be used	PD 54823 10.2.4.	\checkmark	\checkmark

ACS.SMB.004.AC.TABLE 2.CCLP1. INITIAL & RE-ASSESSMENT

				-	
	(\leq 150 mbar) and isolate pressurising source.		C & d)		
(v)	allow 5 minutes pressure equilibrium & note the reading		54823	\checkmark	\checkmark
(vi)	observe gauge for further 5 minutes		.2.4. (e) 54823	\checkmark	
(*)	observe gauge for further 5 minutes		.2.4. (g)	v	v
(vii)	pressure should remain constant		54823	\checkmark	\checkmark
(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	if proceurs has fallen shack each joint with LDE and retest		.2.4. (h) 54823		\checkmark
(viii)	if pressure has fallen check each joint with LDF and retest		.2.4. (i)	V	V
(ix)	A non-discernible drop is achieved and recorded		54823:2016	\checkmark	\checkmark
		10	.2.4 (J)		
(iix)	A Tightness testing of the high pressure side should be 10.3 to 10.3.	2 a h c	d, e ,f ,g & h		
(11, X)	completed at this point	_ u, b, c,		v	v
2	Commissioning testing, appliances can be disconnected or Isolated off on		PD10.2.5		
	their shut off valve , the system purged of air and charged with LPG $$.		D 54823		
			Annov D	/	/
а	purging the supply line		Annex D, D1	\checkmark	\checkmark
b	Testing of the LPG supply line		Annex D	\checkmark	\checkmark
	5,		D.2 D		
(i)	turn off all appliances and isolate supply		.2.1. D.2.5. a)	\checkmark	\checkmark
(i) (ii)	connect U gauge to test fitting, if present, or in-line test tee		D.2.5. b)	v √	
(iii)	gradually turn on main shut-off valve until regulator reaches lock-up pres	sure:	D.2.5. c).	v √	
	close main shut-off valve		1, 2	, v	ľ
(iv)	light one appliance and note drop in gauge. When pressure falls to 5 mba	, close	D.2.5. c).	\checkmark	\checkmark
	appliance tap and isolation valve		3.		
(v)	allow 5 minutes stabilisation, record reading on gauge		D.2.5. c).	\checkmark	\checkmark
(),(i)	allow further 2 minutes, then re-record reading on gauge		4. D.2.5. c).		\checkmark
(vi)	allow further 2 minutes, then re-record reading of gauge		5	v	v
(vii)	if reading in(vi) is not higher than reading in (v), there is no let-by leakag	e	D.2.5. d).	\checkmark	\checkmark
			6, 1,2,3,	/	/
(viii)	What if a discernible pressure drops occurs or there is a smell of gas		D.2.5. e) 1, 2 & 3	\checkmark	\checkmark
3.	Testing of the LPG supply line with appliances PD 54823:2016 Annex D2		1/2 0.0		
(i)	In preparation turn off all appliances but leave on all appliance isolation v		D.2.4	\checkmark	\checkmark
.,	ensure any cooker fold down lids with SSOV are raised – isolate supply	•			
(ii)	connect U gauge to test fitting, if present, or in-line test tee		D.2. 5	\checkmark	\checkmark
(iii)	turn on main shut-off valve to lockup pressure, then close supply valve;		(a & b) D.2. 5	\checkmark	_
(11)			(c 1 & 2)	v	v
(iv)	light one appliance; allow pressure to fall to 30 mbar for propane or 20 m	bar for	D.2. 5	\checkmark	
	butane.		(c 3) note		
(γ)	switch off appliance and leave for $\frac{2}{2}$ 5 minutes temperature stabilization		1 & 2 D.2. 5		\checkmark
(v)	record pressure	_	(c 4)	v	v
(vi)	Wait a further 2 minutes and again record the U gauge reading		D.2.5	\checkmark	\checkmark
(vii)	there should be no discernible pressure drop in system(pipework only) or	within	(c 5) D.2. 5	\checkmark	\checkmark
(*11)	given values (with appliances connected and tested)	witchini	(c 6)	v	v
(viii)	After proving the installation is acceptable		D.2.5.(h)	\checkmark	\checkmark
(ix)	test joints made after test, with LDF		D.2.5. (i)	\checkmark	\checkmark
4.	Tightness testing the high pressure side at this point if needed 10.3 to	10.3.2	a,b,c,d,e,f,g	\checkmark	\checkmark
KNOV			DEE	-	
	VLEDGE AND UNDERSTANDING		REF D.2.1	I	R
1. 2.	correct reading of pressure gauges use of electronic pressure gauge (calibration)		D.2.1 D.2.2		
3.	locating escapes		D.2.5	v √	
		(e 1,2 & 3)	, v	ľ	
					,
4.	dealing with valves letting by, temperature rise or anomalies caused by cylinder			\checkmark	\checkmark
5.	hose pressures equalizing.				\checkmark
J.	determining permissible pressure loss		Annex D Table D1	v	v
6.	tightness testing principles		Section	- /	\checkmark
	agnates testing principles			\checkmark	v
	agnates testing principles		10 and Annex D	V	v

8. Unsafe situations, use of emergency notices and warning labels

PER	FORMANCE CRITERIA	REF	I	R
1.	identify unsafe situations as ID & AR		\checkmark	\checkmark
2.	identify defective appliance(s)/installation(s)		\checkmark	\checkmark
3.	label unsafe appliance(s)/installation(s) appropriately		\checkmark	\checkmark
4.	demonstrate procedure for each unsafe installation as GIUSP			\checkmark
5.	complete warning/advisory notices; explain and issue to appropriate persons			\checkmark
6.				
KNC	WLEDGE AND UNDERSTANDING	REF	Ι	R
1.	explain dealing with ID	Fig 1 & 6.1 GIUSP Edition 7.1	\checkmark	V
2.	explain dealing with AR	Fig 1 & 6.2 GIUSP Edition 7.1	\checkmark	V
2a	explain dealing with AR installations/appliances when turning off does not remove the risk	Fig 1 & 6.2.2 GIUSP Edition 7	\checkmark	V
3.	explain dealing with situations that do not meet current standards but are not unsafe	Foreword GIUSP Edition 7	\checkmark	\checkmark
5. (i)	clearly identify correct notices and labels to be used:			
(ii)	warning notice forms			
(iii)	advisory notices – appliance use, electrical bonding, landlord records		v √	
6.	situations reportable under RIDDOR. Explain reporting to HSE		v √	v √
7.	HSL56: Reg.34 (1) - (3) – Procedures	1	v √	v
8.	GIUSP:		v	
(i)				
(ii)	overall scope			
(11)				

11. Operation and checking of appliances gas safety devices and controls

	FORMANCE CRITERIA – This PC applies only to those safety controls listed in les 1 and 3 of the Practical Provision (ACS.SMB.005.PP.TABLE1)	REF	Ι	R
1.	identify gas safety device/control		\checkmark	\checkmark
2.	check correct operation of each gas safety control/device to MIs or normative documents		\checkmark	\checkmark
3.	identify gas safety controls/devices which are not working correctly by operation, testing and/or visual, audible methods		\checkmark	\checkmark
4.	demonstrate diagnosis of faulty gas safety device/control		\checkmark	\checkmark
5.	isolate gas and/or electrical supplies, where necessary		\checkmark	\checkmark
6.	repair or replace faulty gas safety control/devices		\checkmark	\checkmark
7.	re-establish gas and/or electrical supplies, where necessary		\checkmark	
8.	ensure work carried out is gas tight		\checkmark	
9.	confirm correct operation of repaired/replaced gas safety controls/devices to MIs		\checkmark	
KNO	OWLEDGE AND UNDERSTANDING	REF	Ι	R
1.	appliance data critical for spare part identification of gas safety control/devices		\checkmark	
2.	demonstrate/explain principle of operation of each control/device			
3.	explain sequence of operation of controls/devices e.g. liquid expansion thermostat in line with a liquid expansion FSD		\checkmark	

12. Chimney Standards

VLEDGE AND UNDERSTANDING	REF	I	R
classification of gas flue systems - flueless, open flue, room sealed		\checkmark	\checkmark
chimneys and open gas flue systems: natural draught:			
construction and operation of a chimney /open flue		\checkmark	\checkmark
types of open flue material – cement based, metallic		\checkmark	
methods of jointing open flue and chimney components		\checkmark	
clearances when passing through combustible material		\checkmark	\checkmark
special requirements for terminals and/or guards – protection against wildlife		\checkmark	\checkmark
HSL56:			
Reg.27 Flues (1) to (5)		\checkmark	
Reg.30 Room-sealed appliances (1) to (3)		\checkmark	
	classification of gas flue systems - flueless, open flue, room sealed chimneys and open gas flue systems: natural draught: construction and operation of a chimney /open flue types of open flue material – cement based, metallic methods of jointing open flue and chimney components clearances when passing through combustible material special requirements for terminals and/or guards – protection against wildlife HSL56: Reg.27 Flues (1) to (5)	classification of gas flue systems - flueless, open flue, room sealedinitialchimneys and open gas flue systems: natural draught:initialconstruction and operation of a chimney /open flueinitialtypes of open flue material - cement based, metallicinitialmethods of jointing open flue and chimney componentsinitialclearances when passing through combustible materialinitialspecial requirements for terminals and/or guards - protection against wildlifeinitialHSL56:initialReg.27 Flues (1) to (5)initial	classification of gas flue systems - flueless, open flue, room sealed \checkmark chimneys and open gas flue systems: natural draught: \checkmark construction and operation of a chimney /open flue \checkmark types of open flue material - cement based, metallic \checkmark methods of jointing open flue and chimney components \checkmark clearances when passing through combustible material \checkmark special requirements for terminals and/or guards - protection against wildlife \checkmark HSL56: \checkmark Reg.27 Flues (1) to (5) \checkmark

Issue 14.3 © ACS. SMB April 2018

-	-					
(i	::\	Reg.32 Flue dampers	17	\ +~ /	<u>`</u> ``	
(1 1 (1 (- 5	
()			<u>۲</u>		-	

13. Chimney inspection and testing

PERF	ORMANCE CRITERIA	REF	I	R
1.	visually inspect chimney/flue throughout its length:			
(i)	flue is fit for intended appliance and is classified		\checkmark	\checkmark
(ii)	flue serves only one room or appliance N.B. Assessors may choose to use		\checkmark	\checkmark
	underpinning question/s to cover this PC			
(iii)	secondary flue is correctly positioned and in good condition		\checkmark	\checkmark
(iv)	terminal position meets current legal requirements		\checkmark	\checkmark
(v)	joint between terminal and flue system is weather tight		\checkmark	\checkmark
(vi)	flue is adequately supported			\checkmark
(vii)	flue is clear of obstructions			\checkmark
(viii)	flue is not corroded or cracked			
(ix)	use of bends meets current requirements			
(x)	appliance draught diverter is correctly installed and in good condition			\checkmark
(xi)	flue joints are correctly made			
(xii)	there are no visual signs of spillage of combustion products			
(xiii)	space allocated between flue and combustible material is correct			
(xiv)	seals on balanced natural and fan assisted flues in good condition and correctly installed		\checkmark	\checkmark
(xv)	balanced flue appliance seals in good condition and correctly installed		\checkmark	\checkmark
2.	apply flue flow test (smoke test):			
(i)	check adequate air supply is available to MIs		\checkmark	\checkmark
(ii)	close windows and doors in room or compartment where flue is to be tested		\checkmark	\checkmark
(iii)	pre-warm flue, if necessary		\checkmark	\checkmark
(iv)	position smoke pellet at base of flue being tested		\checkmark	\checkmark
(v)	check smoke is seen to discharge from correct chimney or terminal only		\checkmark	\checkmark
(vi)	check there is no entry of smoke into room/compartment or any other		\checkmark	\checkmark
	room/compartment, roof space or any part, external to flue			
(vii)	rectify any fault found and re-test flue		\checkmark	\checkmark
3.	apply spillage test with appliance connected and in operation:			
(i)	close windows, adjustable vents and doors in room/compartment containing appliance to be tested		\checkmark	\checkmark
(ii)	check ventilation requirements; any mechanical ventilation supplied to room other than combustion air is turned off		\checkmark	\checkmark
(iii)	demonstrate procedures when an extract fan is installed in the property			
(iv)	with appliance in operation at its set input setting, apply smoke match to		\checkmark	\checkmark
	appropriate position in appliance according to MIs			
(v)	check smoke is correctly pulled into appliance flue/chimney system		\checkmark	\checkmark
(vi)	rectify any fault found and re-test appliance (OQ re. testing for spillage with all interconnecting doors open with all fans in operation)		\checkmark	\checkmark
4.	identify defective flue installations - record incorrect flue and ventilation			1
5.	identify defective chimney/flue installations		√	v √
6.	Check room sealed fan assisted positive pressure appliance installation:		v	v
(i)	identify positive pressure appliance			\checkmark
(ii)	fit appliance case (case screws, seals, items trapped between case seal and		V	
	appliance etc.)			
7.	check room sealed fan assisted positive pressure appliance case seals for possible leakage of products of combustion		\checkmark	\checkmark
(i)	set appliance controls to their highest setting and light burner		\checkmark	\checkmark
(ii)	initially check case seal by running hand around boiler case and back plate (OQ re.		\checkmark	\checkmark
(iii)	corroded/damaged back plate) light a match/taper and position flame very close to case seal or any possible leakage point		\checkmark	\checkmark
(iv)	move match/taper around entire seal, inc. bottom of case		\checkmark	\checkmark
(v)	identify any leakage of products of combustion		√	v
8.	inspection requirements for fanned flues in voids	TB 008 ED3 2013	V	V
KNO	WLEDGE AND UNDERSTANDING	REF	I	R
1.	types of room sealed positive pressure combustion chamber appliances			
2.	causes of leakage of products of combustion from room sealed fan assisted			
2.	positive pressure appliances		v	
3.	checks on room sealed fan assisted positive pressure appliances prior to fitting the		\checkmark	
4	case, inc. back plate inspection, appliance case screws, case seals etc.		_/	
4.	installation and spillage testing new or used appliances when MIs are not available		\checkmark	

 \checkmark

ACS.SMB.004.AC.TABLE 2.CCLP1. INITIAL & RE-ASSESSMENT

5.	alternative methods of compliance when inspection hatches are not available for flues in voids	TB 008 ED3 2013	\checkmark	\checkmark
6.	Actions required where fumes, smells or spillage have been reported/encountered	BS7967 2015 6.1	\checkmark	\checkmark

14. Installation of open, closed, balanced and fan assisted chimneys

PER	FORMANCE CRITERIA	REF	Ι	R
1.	cement based and/or metallic rigid:			
(i)	chimney /flue pipe jointing		\checkmark	\checkmark
(ii)	chimney /flue pipe adapters		\checkmark	\checkmark
(iii)	chimney /flue pipe bends		\checkmark	\checkmark
(iv)	chimney /flue pipe supports		\checkmark	\checkmark
(v)	spacing between flue pipe or chimney and combustible material		\checkmark	\checkmark
2.	plastic flue pipe - chimney /flue pipe jointing		\checkmark	\checkmark
3.	identify room sealed flue installation -correct and incorrect installations:			
(i)	chimney /flue duct cuts		\checkmark	\checkmark
(ii)	assemble, adjust and seal to MIs		\checkmark	\checkmark
(iii)	chimney/ flue terminal guards against the room sealed flue terminal			\checkmark
KNO	WLEDGE AND UNDERSTANDING	REF	Ι	R
1.	insulation for open flues /chimneys		\checkmark	
2.	chimney /flue guards for room sealed flue terminals		\checkmark	\checkmark
3.	heat shields for room sealed flue terminals		\checkmark	\checkmark

15. Re-establish existing LPG supply and relight appliances

PERF	ORMANCE CRITERIA	REF	Ι	R
1.	check installation is gas tight		\checkmark	\checkmark
2.	re-establish gas supply		\checkmark	\checkmark
3.	check changeover valve is operating correctly		\checkmark	
4.	appliance(s) is/are visually checked and re-lit inc.:			
(i)	purge system and appliances of air		\checkmark	\checkmark
(ii)	re-light appliance(s)		\checkmark	\checkmark
(iii)	confirm satisfactory operation of user controls		\checkmark	\checkmark
(iv)	visually inspect appliance installation(s) for unsafe situations		\checkmark	\checkmark
KNO	WLEDGE AND UNDERSTANDING	REF	Ι	R
1.	describe correct action when an un-commissioned appliance is identified		\checkmark	
2.	confirm actions if pipework and appliance(s) are not tested (commissioned) when gas supply is re-established		\checkmark	
3.	HSL56: Reg.33 Testing of appliances 33(1) to (3)		\checkmark	